SI. No.	Description	Unit	Qty	Scope of Supply	Installation	Erection Supervision, Testing & Commissioning	Remarks	Unit Rate	Spec	Amount
1	Shifting, Installation, Testing and Commissioning of 2.5MVA, 6.6/0.433kV,50HZ,Dyn11,3 Phase, 2 winding, Core type Cast Resin Dry type transformer.	Nos.	1	JSOL	Bidder	Bidder	Remarks -1	4900.00	spec- 1	4900.00
2	Shifting, Installation, Testing and Commissioning of 250kVA, 415/415V Cast Resin Dry type Lighting transformers. Vector group- Dyn11, 3 phase 50hz.	Nos.	2	JSOL	Bidder	Bidder	Remarks -2	1700.00	spec- 1	3400.00
3	Shifting, Installation, Testing and Commissioning of 100kVA, 415/415V Cast Resin Dry type Lighting transformers. Vector group- Dyn11, 3 phase 50hz.	Nos.	1	JSOL	Bidder	Bidder	Remarks -3	3200.00	spec- 1	3200.00
4	Installation, Testing and Commissioning of 6.6KV/ √3, NGR Size - 1400 (Width) X 850 (Depth) X 1150 (Height) mm	Nos.	2	JSOL	Bidder	Bidder	Remarks -4	48000.00	spec- 1	96000.00
JSOL	Bidder	Bidder	Remarks -5	spec-1						
JSOL	Bidder	Bidder	Remarks -6	spec-1						